



Individual relaxation and distraction

RELAX includes products made of hard foam support material for bathrooms and spa areas:

Relaxation loungers (RELAX-RL) and massage tables (RELAX-MT) in different design variants.

Tileable bath tub building kits (RELAX-BWV) and footbaths with seat (RELAX-FB), each including drainage technology.

Building kits for shower design variants. (RELAX-RD, RELAX-SD, RELAX-RSE, RELAX-JUNIOR).


Accessories such as prefabricated niches (RELAX-NI), bench seats for the shower area (RELAX-BA), curbs (RELAX-CU) and ramps (RELAX-RP) for shower bases with a step (Step-Up).



LUX ELEMENTS®-RELAX-PLUS

LUX ELEMENTS manufactures individual customised and special products for the RELAX product group.

These include dimensions, thicknesses, shapes etc. that deviate from the standard program. For more information see page 8.















RELAX-RL – relaxation loungers

There is a choice of four relaxation loungers of hard foam support material to extend the wellness area. They are available with or without an electrical heating system.



■ PRODUCT SPECIFICATIONS – LUX ELEMENTS®-RELAX-RL

	ARTICLE-NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	NOMINAL FORMATS/DIMENSIONS LENGTH x WIDTH x HEIGHT	UNIT
	LREL2001	RELAX-RL-DREAM O Relaxation lounger, construction made of hard foam support elements, without heating	1853 x 700 x 944 mm	piece
	LREL2002	RELAX-RL-DREAM M Relaxation lounger, construction made of hard foam support elements, with heating, electrical, incl. thermostatic controller	1853 x 700 x 944 mm	piece
	LREL2003	RELAX-RL-COMFORT O Relaxation lounger, construction made of hard foam support elements, without heating	1927 x 700 x 873 mm	piece
	LREL2004	RELAX-RL-COMFORT M Relaxation lounger, construction made of hard foam support elements, with heating, electrical, incl. thermostatic controller	1927 x 700 x 873 mm	piece
	LREL2005	RELAX-RL-ENJOY O Relaxation lounger, construction made of hard foam support elements, without heating	1776 x 700 x 931 mm	piece
	LREL2006	RELAX-RL-ENJOY M Relaxation lounger, construction made of hard foam support elements, with heating, electrical, incl. thermostatic controller	1776 x 700 x 931 mm	piece
	LREL2007	RELAX-RL-FIGURA O Relaxation lounger, construction made of hard foam support elements, without heating	1961 x 700 x 874 mm	piece
	LREL2008	RELAX-RL-FIGURA M Relaxation lounger, construction made of hard foam support elements, with heating, electrical, incl. thermostatic controller	1961 x 700 x 874 mm	piece



LUX ELEMENTS®-RELAX

RELAX-MT – massage tables

Two massage tables are offered for enhancing the spa area.



Both variants are equipped with a maintenance opening. This enables access to optional equipment such as heating, a water connection or drainage technology.

■ RELAX-MT-SANA



Dimensions:
1900 x 740 x 750 mm

■ RELAX-MT-SOMNO

Dimensions:
2100 x 940 x 750 mm



■ PRODUCT SPECIFICATIONS – LUX ELEMENTS®-RELAX-MT

	ARTICLE- NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	NOMINAL FORMATS/DIMENSIONS LENGTH x WIDTH x HEIGHT	UNIT
	LREL8300	RELAX-MT-SANA Massage table with inspection opening, prefabricated from hard foam support material	1900 x 740 x 750 mm	piece
	LREL8301	RELAX-MT-SOMNO Massage table with inspection opening, prefabricated from hard foam support material	2100 x 940 x 750 mm	piece

System components COL, DRY - current price list page 63

RELAX-FB – foot basins

Integrated solution consisting of pre-fabricated footbath with maintenance opening, including drainage technology, bench seat and substrate element to suit footbath and bench seat.

■ RELAX-FB-UNO



Foot basin with inspection opening, with drain incl. siphon and standpipe valve 250 mm, dimensions: 580 x 580 x 320 mm

■ RELAX-FB-BA-UNO




Bench seat for foot basin RELAX-FB-UNO, dimensions: 580 x 580 x 500 mm

■ RELAX-FB-U-UNO

Substructure for foot basin RELAX-FB-UNO and for bench RELAX-FB-BA-UNO, dimensions: 580 x 580 x 120 mm



■ PRODUCT SPECIFICATIONS – LUX ELEMENTS®-RELAX-FB

	ARTICLE-NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	NOMINAL FORMATS/DIMENSIONS LENGTH x WIDTH x HEIGHT	UNIT
	LREL8400	RELAX-FB-UNO Foot basin with inspection opening, prefabricated from hard foam support material, with drain incl. siphon and standpipe valve 250 mm	580 x 580 x 320 mm	piece
	LREL8402	RELAX-FB-BA-UNO Bench seat for foot basin RELAX-FB-UNO, prefabricated from hard foam support material	580 x 580 x 500 mm	piece
	LREL8401	RELAX-FB-U-UNO Substructure for foot basin RELAX-FB-UNO and for bench RELAX-FB-BA-UNO, prefabricated from hard foam support material	580 x 580 x 120 mm	piece



RELAX-BW – bath tub construction kit


RELAX-BW are tileable bath tub construction kits, with drain and overflow fittings and substrate element, in two different sizes.

Also available as additional fittings for the interior are two inlay elements in various designs.







Inlay elements


The inlay elements, with the variants 'Headrest' and 'Triangle' can be installed on one or both sides.



■ PRODUCT SPECIFICATIONS – LUX ELEMENTS®-RELAX-BW


	ARTICLE-NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	NOMINAL FORMATS/DIMENSIONS LENGTH x WIDTH x HEIGHT	UNIT
	LREL3001	RELAX-BW 1800–2000 Bath tub construction kit, tileable, incl. drain and overflow fitting and base element	1800–2000 x 800 x 600 mm	piece
	LREL3002	RELAX-BW 2000–2200 Bath tub construction kit, tileable, incl. drain and overflow fitting and base element	2000–2200 x 800 x 600 mm	piece
	LREL3101	RELAX-BW EK Bath tub mounting part suitable for both tub sides, 'Headrest' design	357 x 630 x 455 mm	piece
	LREL3102	RELAX-BW ED Bath tub mounting part suitable for both tub sides, 'Triangle' design	300 x 630 x 455 mm	piece
	LREL3901	RELAX-KIT BW Mounting kit for RELAX-BW: 23,5 kg DRY-ASK (1 x 20 kg + 1 x 3,5 kg), 10 m DRY-DB, 4 pieces DRY-DBIE, 2 cartridges COL-MK, 10 m ARM-100 SK, 25 kg COL-AK		Kit

System components ARM, COL, DRY · current price list page 65



RELAX-RD – the round shower

RELAX-RD is a building kit for a round shower with the following components:



RELAX-DRD	Dimensions	Ø
Thickness	40 mm	1240 mm

Hard-foam cover element FLAT to fit RELAX-RDW

RELAX-RDW	Dimensions
Overall height	2500 mm
Material thickness	80 mm
Outer diameter	1240 mm
Inner diameter	1080 mm
Entrance width (without AE)	approx. 560 mm
Entrance width (with AE)	approx. 405 mm
Inner surface measurement	7,41 m ²
Outer surface measurement	8,05 m ²

Hard-foam shower partition wall elements as kit in 3 segments

DECO-AE	Dimensions	Ø
Length	2500 mm	120 mm

Hard foam finishing element, see product group DECO (page 158)

RELAX-BORD 50	Dimensions	Ø
Thickness	30/45 mm	1240 mm
Square measure floor	0,92 m ²	

Hard foam shower base element to fit RELAX-RDW





RELAX-UBORD 50	Dimensions	Ø
Thickness	55 mm	1240 mm

Substrate element for RELAX-BORD 50

Instruction for installing the shower doors: When planning to install a shower door, a FIX-PRO-MAK (see page 173) hard plastic insert can be pre-assembled at the factory for fitting the door fastening on a custom-made basis.


RELAX-RD – roofs

Roofs in the FLAT and CLASSIC design variants are suitable for RELAX-RD.



The overall height (roofs including RELAX-RDW) is:

Design FLAT: 2540 mm
Design CLASSIC: 2600 mm





LUX ELEMENTS®-RELAX

RELAX-RD – accessories

RELAX-PA

Panel, rounded back suitable for RELAX-RDW with integrated FIX-PRO-MAK strip for fixation of the shower rod and accessories.

Alternatively, the **FIX-IPA-...** installation panel is also suitable for mounting the fittings (as an integrated or individual variant, see page 174).



RELAX-KIT RD

Suitable mounting kits are provided for RELAX-RD installation and set-up with LUX ELEMENTS shower base element (RELAX-KIT-SDM) or without floor (RELAX-KIT-SDO).




RELAX-KIT-RDM




RELAX-KIT-RDO

Suitable accessories are provided for RELAX-RD, e.g. a concave trim for connection to the wall and finishing elements for the edges. For more information please see product group DECO (beginning page 158).



■ PRODUCT SPECIFICATIONS – LUX ELEMENTS®-RELAX-RD

	ARTICLE-NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	NOMINAL FORMATS/DIMENSIONS LENGTH x WIDTH x HEIGHT	UNIT
--	----------------	------------------------------------	---	------




	LREL4001	RELAX-BORD 50 Hard foam shower base element, with integrated and sealed floor drain support 135 x 135 mm in the centre; for round shower RELAX-RDW; for floor drain supports, see floor drain systems (page 68–75)	Ø 1240 x 30/45 mm	piece
	LREL4002	RELAX-UBORD 50 Substrate element for RELAX-BORD 50, round	Ø 1240 x 55 mm	piece
	LREL4000	RELAX-RDW Hard-foam shower partition wall elements to fit RELAX-BORD 50, round, wall thickness 80 mm as kit in 3 segments	Inner diameter: 1080 mm; Height: 2500 mm	set
	LREL4005	RELAX-PA Panel, rounded back, with integrated FIX-PRO-MAK strips for the installation of shower rod and accessories	2500 x 350 x 34/5 mm	piece
	LREL4003	RELAX-DRD Hard-foam cover element FLAT to fit RELAX-RD	Ø 1240 mm x 40 mm	piece
	LREL4004	RELAX-DCRD Hard-foam cover element CLASSIC to fit RELAX-RD	Ø 1640 mm x 100 mm	piece
	LREL4006	RELAX-KIT RDM Mounting kit for RELAX-RD with RELAX-BORD 50: 10 m ARM-100 SK, 4 cartridges COL-MK, 5 x 5 kg COL-AK		Kit
	LREL4007	RELAX-KIT RDO Mounting kit for RELAX-RD without base: 10 m ARM-100 SK, 3 cartridges COL-MK, 3 x 5 kg COL-AK		Kit

System components ARM, COL, DRY · accessories see DECO page 158 · current price list page 66



RELAX-SD – the curved shower

RELAX-SD is a building kit for a curved shower, left-curving or right-curving, with the following components:




RELAX-DSD	Dimensions
Thickness	40 mm

Hard-foam cover element FLAT to fit RELAX-SDW

RELAX-SDW	Dimensions
Overall height	2500 mm
Overall width	1965 mm
Overall depth	1440 mm
Inner width	1805 mm
Inner depth	1280 mm
Entrance width	ca. 636 mm
Material thickness	80 mm
Inner surface measurement	11,79 m ²
Outer surface measurement	12,64 m ²

Hard-foam shower partition wall elements as kit in 6 segments



DECO-AE	Dimensions	Ø
Length	2500 mm	120 mm

Hard foam finishing element, see product group DECO (page 158)

RELAX-BOSD 50 L/R	Dimensions
Thickness	30/45 mm
Square measure floor	1,71 m ²

Hard foam shower base element to fit RELAX-SDW





RELAX-UBOSD 50 L/R	Dimensions
Thickness	55 mm

Substrate element for RELAX-BOSD 50 L/R

***Note:** the fittings are to be located in the shower area.

RELAX-SD – roofs

Roofs in the FLAT and CLASSIC design variants are suitable for RELAX-SD.



The overall height (roofs including RELAX-SDW) is:

Design FLAT: 2540 mm
Design CLASSIC: 2600 mm





LUX ELEMENTS®-RELAX

RELAX-SD – accessories

RELAX-PA

Panel, rounded back suitable for RELAX-SDW with integrated FIX-PRO-MAK strip for fixation of the shower rod and accessories.

Alternatively, the **FIX-IPA-...** installation panel is also suitable for mounting the fittings (as an integrated or individual variant, see page 174).





RELAX-KIT SD

Suitable mounting kits are provided for RELAX-SD installation and set-up with LUX ELEMENTS shower base element (RELAX-KIT-SDM) or without floor (RELAX-KIT-SDO).




■ PRODUCT SPECIFICATIONS – LUX ELEMENTS®-RELAX-SD

ARTICLE-NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	NOMINAL FORMATS/DIMENSIONS LENGTH x WIDTH x HEIGHT	UNIT
----------------	------------------------------------	---	------




	LREL5001	RELAX-BOSD 50 L Hard foam shower base element, square measure floor 1,71 m², with integrated and sealed floor drain support frame 135 x 135 mm, left-curving, for curved shower RELAX-SDW; for floor drain supports, see floor drain systems (page 68–75)	1965 x 1440 x 30/45 mm	piece
	LREL5002	RELAX-UBOSD 50 L Substrate element for RELAX-BOSD 50 L left-curving	1965 x 1440 x 55 mm	piece
	LREL5003	RELAX-BOSD 50 R Hard foam shower base element, square measure floor 1,71 m², with integrated and sealed floor drain support frame 135 x 135 mm, right-curving, for curved shower RELAX-SDW; for floor drain supports, see floor drain systems (page 68–75)	1965 x 1440 x 30/45 mm	piece
	LREL5004	RELAX-UBOSD 50 R Substrate element for RELAX-BOSD 50 R right-curving	1965 x 1440 x 55 mm	piece
	LREL5000	RELAX-SDW Hard-foam shower partition wall element to fit RELAX-BOSD 50 L and R, curved, wall thickness 80 mm, as kit in 6 segments	Height: 2500 mm	set
	LREL4005	RELAX-PA Panel, rounded back, with integrated FIX-PRO-MAK strips for the installation of shower rod and accessories	2500 x 350 x 34/5 mm	piece
	LREL5005	RELAX-DSD Hard-foam cover element FLAT to fit RELAX-SD	40 mm thickness	piece
	LREL5006	RELAX-DCSD R Hard-foam cover element CLASSIC to fit RELAX-SD right-curving	2365 x 1840 x 100 mm	piece
	LREL5007	RELAX-DCSD L Hard-foam cover element CLASSIC to fit RELAX-SD left-curving	2365 x 1840 x 100 mm	piece
	LREL5008	RELAX-KIT SDM Mounting kit for RELAX-SD with BOSD 50: 30 m ARM-100 SK, 8 cartridges COL-MK, 2 x 25 kg COL-AK		Kit
	LREL5009	RELAX-KIT SDO Mounting kit for RELAX-SD without base: 30 m ARM-100 SK, 5 cartridges COL-MK, 4 x 5 kg COL-AK		Kit

System components ARM, COL, DRY · accessories see DECO page 158 · current price list page 68



RELAX-RSE – the space-saving corner shower

RELAX-RSE is a building kit for a space-saving corner shower with two offset walls. This is available either with two high walls or optionally with one high and one half-high wall with shelving.



RELAX-RSE H	Dimensions
Overall height	2500 mm
Overall width	1850 mm
Overall depth	1130 mm
Inner width	1770 mm
Inner depth	1050 mm
Entrance width	640 mm
Material thickness	80 mm
Inner surface measurement	6,12 m ²
Outer surface measurement	6,02 m ²

2 hard foam shower partition wall elements (each 2500 mm height) as kit

RELAX-RSE A	Dimensions
Overall height	2500 mm
Overall width walls	1850 mm
Overall width incl. shelf	1950 mm
Overall depth	1130 mm
Inner width	1770 mm
Inner depth	1050 mm
Entrance width	640 mm
Material thickness	80 mm
Inner surface measurement	4,54 m ²
Outer surface measurement	4,60 m ²

2 hard foam shower partition wall elements (2500 mm, 1200 mm + shelf) as kit

DECO-AE	Dimensions	Ø
Length	2500 mm	120 mm


See product group DECO (page 158). The application of DECO-AE is not possible on the half side when using the shelf.

RELAX-BORSE 50 L/R	Dimensions
Thickness	30/45 mm
Square measure floor	1,83 m ²

Hard foam shower base element to fit RELAX-RSE H and RELAX-RSE A








RELAX-UBORSE 50 L/R	Dimensions
Thickness	55 mm

Substrate element for RELAX-BORSE 50 L/R



***Note:** the fittings are to be located in the shower area.

■ PRODUCT SPECIFICATIONS – LUX ELEMENTS®-RELAX-RSE

	ARTICLE-NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	NOMINAL FORMATS/DIMENSIONS LENGTH x WIDTH x HEIGHT	UNIT
   <p>RELAX-RSE-H RELAX-RSE-A</p>				
  <p>RELAX-BORSE 50 L RELAX-RSE-A</p>	LREL6002	RELAX-BORSE 50 L Hard foam shower base element, with integrated and sealed floor drain support frame 135 x 135 mm; left-curving, for space-saving corner showers RELAX-RSE-H and RELAX-RSE-A; for floor drain supports, see floor drain systems (page 68–75)	1850 x 1130 x 30/45 mm	piece
	LREL6003	RELAX-UBORSE 50 L Substrate element for RELAX-BORSE 50 L, left-curving	1850 x 1130 x 55 mm	piece
	LREL6004	RELAX-BORSE 50 R Hard foam shower base element, with integrated and sealed floor drain support frame 135 x 135 mm; right-curving, for space-saving corner showers RELAX-RSE-H and RELAX-RSE-A; for floor drain supports, see floor drain systems (page 68–75)	1850 x 1130 x 30/45 mm	piece
	LREL6005	RELAX-UBORSE 50 R Substrate element for RELAX-BORSE 50 R, right-curving	1850 x 1130 x 55 mm	piece
	LREL6000	RELAX-RSE-H 2 hard foam shower partition wall elements, each 2500 mm in height, matches RELAX-BORSE 50 L and R, wall thickness 80 mm, as a kit	2500/2500 mm height, 80 mm thickness	set
	LREL6001	RELAX-RSE-A 2 hard foam shower partition wall elements, 1 x 2500 mm in height, 1 x 1200 mm in height plus shelf, matches RELAX-BORSE 50 L and R, wall thickness 80 mm, as a kit	2500/1200 mm height, 80 mm thickness	set
	LREL6006	RELAX-KIT RSEM Mounting kit for RELAX-RSE with RELAX-BORSE 50: 10 m ARM-100 SK, 4 cartridges COL-MK, 30 kg COL-AK, 10 m DRY-DB, 1 piece DRY-DBIE, 3,5 kg DRY-ASK		Kit
	LREL6007	RELAX-KIT RSEO Mounting kit for RELAX-RSE without base: 10 m ARM-100 SK, 2 cartridges COL-MK, 3 x 5 kg COL-AK		Kit


System components ARM, COL, DRY · accessories see DECO page 158 · current price list page 70



LUX ELEMENTS®-RELAX

RELAX-JUNIOR

RELAXJUNIOR is a building kit in two sizes complete with glass door for a corner shower. The RELAX-JA mounted part allows the RELAX-JS standard version to be increased in size.



RELAX-JS	Dimensions
Overall height	2500 mm
Overall width	1260 mm
Overall depth	1000 mm
Inner width	1180 mm
Inner depth	920 mm
Entrance width	approx. 700 mm
Material thickness	80 mm
Inner surface measurement	3,18 m ²
Outer surface measurement	3,30 m ²

Hard-foam shower partition wall elements as kit in 2 segments

RELAX-JS + RELAX-JA	Dimensions
Overall height	2500 mm
Overall width	1450 mm
Overall depth	1000 mm
Inner width	1370 mm
Inner depth	920 mm
Entrance width	approx. 700 mm
Material thickness	80 mm
Inner surface measurement	3,85 m ²
Outer surface measurement	3,77 m ²

Hard-foam shower partition wall elements as kit in 2 segments + attachment

RELAX-DOOR-BS	Dimensions
Glas width	683 mm
Glas height	1890 mm
Installation dimension width	690 mm

Glass door ESG 8 mm







Dimensions	RELAX-BOJS L/R	RELAX-UBOJS L/R
Thickness	30/45 mm	55 mm
Square measure floor	1,18 m ²	


Hard foam shower element / substrate element for RELAX-JS

Dimensions	RELAX-BOJSA L/R	RELAX-UBOJSA L/R
Thickness	30/45 mm	55 mm
Square measure floor	1,37 m ²	

Hard foam shower element / substrate element for RELAX-JS + RELAX-JA

The products DECO-HK 100 or DECO-HK 200 (page 160) are suitable to round off corners to the wall or within the RELAX-JUNIOR (see illustration above).






LUX ELEMENTS®-RELAX

■ PRODUCT SPECIFICATIONS – LUX ELEMENTS®-RELAX-JUNIOR



ARTICLE-NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	NOMINAL FORMATS/DIMENSIONS LENGTH x WIDTH x HEIGHT	UNIT
----------------	------------------------------------	---	------




	LREL7002	RELAX-BOJS L Hard foam shower base element, with integrated and sealed floor drain support frame 135 x 135 mm, for corner shower RELAX-JS in left-hand corner; for floor drain supports, see floor drain systems (page 68–75)	1260 x 1000 x 30/45 mm	piece
	LREL7003	RELAX-UBOJS L Substrate element for RELAX-BOJS L	1260 x 1000 x 55 mm	piece
	LREL7004	RELAX-BOJSA L Hard foam shower base element, with integrated and sealed floor drain support frame 135 x 135 mm, for corner shower RELAX-JS in combination with RELAX-JA in left-hand corner; for floor drain supports, see floor drain systems (page 68–75)	1460 x 1000 x 30/45 mm	piece
	LREL7005	RELAX-UBOJSA L Substrate element for RELAX-BOJSA L	1460 x 1000 x 55 mm	piece
	LREL7006	RELAX-BOJS R Hard foam shower base element, with integrated and sealed floor drain support frame 135 x 135 mm, for corner shower RELAX-JS in right-hand corner; for floor drain supports, see floor drain systems (page 68–75)	1260 x 1000 x 30/45 mm	piece
	LREL7007	RELAX-UBOJS R Substrate element for RELAX-BOJS R	1260 x 1000 x 55 mm	piece
	LREL7008	RELAX-BOJSA R Hard foam shower base element, with integrated and sealed floor drain support frame 135 x 135 mm, for corner shower RELAX-JS in combination with RELAX-JA in right-hand corner; for floor drain supports, see floor drain systems (page 68–75)	1460 x 1000 x 30/45 mm	piece
	LREL7009	RELAX-UBOJSA R Substrate element for RELAX-BOJSA R	1460 x 1000 x 55 mm	piece
	LREL7000	RELAX-JS Hard foam shower partition wall element, matches RELAX-BOJS, curved, as a kit in 2 segments	2500 mm height, 80 mm thickness	set
	LREL7001	RELAX-JA Hard foam shower partition wall extension element incl. FIX-PRO-MAK strips for door fitting	2500 x 190 x 80 mm	piece
	LREL7010	RELAX-DOOR-BS Glass door ESG 8 mm, incl. hinge plates and stainless steel handle, right and left hinged installation	Installation dimension: 690 mm, glass width: 683 mm, glass height: 1890 mm	piece

Contd. on page 123

■ PRODUCT SPECIFICATIONS – LUX ELEMENTS®-RELAX-JUNIOR

	ARTICLE-NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	NOMINAL FORMATS/DIMENSIONS LENGTH x WIDTH x HEIGHT	UNIT
	LREL7011	RELAX-KIT-JM Mounting kit for RELAX-JUNIOR with RELAX-BOJS or RELAX-BOJSA: 10 m ARM-100 SK, 3 cartridges COL-MK, 25 kg COL-AK, 10 m DRY-DB, 3 pieces DRY-DBIE, 3,5 kg DRY-ASK		Kit
	LREL7012	RELAX-KIT-JO Mounting kit for RELAX-JUNIOR without base: 10 m ARM-100 SK, 3 cartridges COL-MK, 3 x 5 kg COL-AK		Kit

System components ARM, COL, DRY · accessories see DECO page 158 · current price list page 72



RELAX-NI – niches

Niches are an elegant and space-saving option for storage. Unlike protruding shelves, they are integrated into the wall. As a design element, niches make a wall surface visually more interesting.

RELAX-NI are prefabricated niches in four formats:

■ RELAX-NI-S

Dimensions: 203 x 406 x 89 mm,
interior dimension: 102 x 305 x 77 mm

■ RELAX-NI-M



Dimensions: 406 x 406 x 89 mm,
interior dimension: 305 x 305 x 77 mm

■ RELAX-NI-L




Dimensions: 559 x 406 x 89 mm,
interior dimension: 457 x 305 x 77 mm,
including 1 loose shelf


■ RELAX-NI-XL

Dimensions: 1070 x 406 x 89 mm,
interior dimension: 968 x 178 x 77 mm,
including 2 loose shelves



■ PRODUCT SPECIFICATIONS – LUX ELEMENTS®-RELAX-NI

	ARTICLE-NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	NOMINAL FORMATS/DIMENSIONS LENGTH x WIDTH x HEIGHT	UNIT
   				
		RELAX-NI-S		
		RELAX-NI-M		
		RELAX-NI-L		
		RELAX-NI-XL		
	LREL8200	RELAX-NI-S Prefabricated niches made of hard foam support material	203 x 406 x 89 mm	piece
	LREL8201	RELAX-NI-M Prefabricated niches made of hard foam support material	406 x 406 x 89 mm	piece
	LREL8202	RELAX-NI-L Prefabricated niches made of hard foam support material, including 1 loose shelf	559 x 406 x 89 mm	piece
	LREL8203	RELAX-NI-XL Prefabricated niches made of hard foam support material, including 2 loose shelves	1070 x 406 x 89 mm	piece



LUX ELEMENTS®-RELAX

RELAX-BA – benches

Since bath tubs are being replaced more and more by flush with the floor showers, shower areas are becoming larger and offer space for an additional seat.

RELAX-BA are prefabricated seats for the corner in a compact or 'floating' design as well as a wall-mounting bench seat in two widths.



■ RELAX-BA-SOLO-G

Bench form straight

RELAX-BA-SOLO-G 900 900 x 500 x 450 mm

RELAX-BA-SOLO-G 750 750 x 500 x 450 mm

To match TUB-BOL (page 60) and
TUB-LINE BOL (page 84).



RELAX-BA-SOLO-G

■ RELAX-BA-CO

Bench form CORNER, triangular

RELAX-BA-CO 816 x 577 x 508 mm



RELAX-BA-CO

■ RELAX-BA-CO FLOAT

Bench form CORNER, floating, flexible height,
incl. mounting kit consisting of 6 pieces FIX-SB 80S35,
4 pieces FIX-SD 80 and 1 cartridge COL-MK






RELAX-BA-CO FLOAT S 610 x 430 x 100 mm

RELAX-BA-CO FLOAT L 864 x 610 x 100 mm




RELAX-BA-CO FLOAT

■ PRODUCT SPECIFICATIONS – LUX ELEMENTS®-RELAX-BA

	ARTICLE-NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	NOMINAL FORMATS/DIMENSIONS LENGTH x WIDTH x HEIGHT	UNIT
	LREL8003	RELAX-BA-SOLO-G 900 Bench form SOLO, straight, 900 mm long	900 x 500 x 450 mm	piece
	LREL8004	RELAX-BA-SOLO-G 750 Bench form SOLO, straight, 750 mm long	750 x 500 x 450 mm	piece
	LREL8000	RELAX-BA-CO Bench form CORNER, triangular	816 x 577 x 508 mm	piece
	LREL8001	RELAX-BA-CO FLOAT S Bench form CORNER FLOAT S, floating, including mounting kit consisting of 6 pieces FIX-SB 80S35, 4 pieces FIX-SD 80 and 1 cartridge COL-MK	610 x 430 x 100 mm	piece
	LREL8002	RELAX-BA-CO FLOAT L Bench form CORNER FLOAT L, floating, including mounting kit consisting of 6 pieces FIX-SB 80S35, 4 pieces FIX-SD 80 and 1 cartridge COL-MK	864 x 610 x 100 mm	piece

System components COL, DRY · current price list page 75



LUX ELEMENTS®-RELAX

RELAX-CU – curbs

Prefabricated shower curbs in various lengths for use as water stops for shower bases with a step (Step-Up). For the protection of the floor and bathroom against splash water.



The curbs can be adapted to fit any shower base dimensions by simply cutting to size.

■ RELAX-CU-F-5



Dimensions:
1524 x 114 x 130/127 mm

■ RELAX-CU-F-8

Dimensions:
2438 x 114 x 130/127 mm



■ PRODUCT SPECIFICATIONS – LUX ELEMENTS®-RELAX-CU

	ARTICLE-NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	NOMINAL FORMATS/DIMENSIONS LENGTH x WIDTH x HEIGHT	UNIT
	LREL8100	RELAX-CU-F-5 Curb F 5, prefabricated from hard foam support material	1524 x 114 x 130/127 mm	piece
	LREL8101	RELAX-CU-F-8 Curb F 8, prefabricated from hard foam support material	2438 x 114 x 130/127 mm	piece

System components COL, DRY - current price list page 76

RELAX-RP – ramps

Prefabricated ramps in two widths with different gradients and a length of 1828 mm for a barrier-free transition from bathroom floor to a shower base with a step (Step-Up).




The ramps can be adapted to fit any shower base dimensions by simply cutting to size.

■ RELAX-RP-M



Gradient: 19,2 %,
dimensions:
1828 x 204 x 45 mm


■ RELAX-RP-L

Gradient: 12,8 %,
dimensions:
1828 x 304 x 45 mm



■ PRODUCT SPECIFICATIONS – LUX ELEMENTS®-RELAX-RP

	ARTICLE-NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	NOMINAL FORMATS/DIMENSIONS LENGTH x WIDTH x HEIGHT	UNIT
	LREL8204	RELAX-RP-M Ramp M, prefabricated from hard foam support material	1828 x 204 x 45 mm	piece
	LREL8205	RELAX-RP-L Ramp L, prefabricated from hard foam support material	1828 x 304 x 45 mm	piece



LUX ELEMENTS®-RELAX




LUX ELEMENTS®-RELAX-PLUS

LUX ELEMENTS manufactures individual customised and special products for the RELAX product group. These include dimensions, thicknesses, shapes etc. that deviate from the standard program. For more information see page 8.




Photographer: Jeroen Kuppens





Prefabricated room constructions

Firmly defined room constructions made of hard foam support material, consisting of floor element, walls including door, seat and roof element. The cabins are offered as building kits in various sizes with square, pentagonal or rectangular designs.








MODUL-CAB – the construction

A building kit for cabins from the MODUL product group is comprised of the following components:

- Roof (roof form FLAT)
- Wall construction as kit (wall thickness 50 mm, height 2390 mm),
- Glass door (DOOR-GTF-TK) with door knob (DOOR-TK)
- Flat frame (DOOR-TZ F-S)
- Floor element with floor drain support frame 135 x 135 mm

Enhancements are possible with optional accessories such as a steam inlet or installation panel (see page 174). Assembly accessories are offered as complete kits for all available sizes.


See page 141 for technical information concerning the connection.




Floor drain systems see page 68–75

■ MODUL-CAB-Q
quadratic cabin

Article	Dimensions
MODUL-CAB-Q 1180	1180 x 1180 x 2390 mm
MODUL-CAB-Q 1450	1450 x 1450 x 2390 mm




MODUL-CAB Q




■ MODUL-CAB-F
pentagonal cabin

Article	Dimensions
MODUL-CAB-F 1180	1180 x 1180 x 2390 mm
MODUL-CAB-F 1450	1450 x 1450 x 2390 mm




MODUL-CAB F




■ MODUL-CAB-R
rectangular cabin

Article	Dimensions
MODUL-CAB-R 1800/900	1800 x 900 x 2390 mm
MODUL-CAB-R 1800/1180	1800 x 1180 x 2390 mm
MODUL-CAB-R 2065/1180	2065 x 1180 x 2390 mm
MODUL-CAB-R 2370/1450	2370 x 1450 x 2390 mm



MODUL-CAB R



■ MODUL-CAB-KIT

MODUL-KIT-CAB 1

Mounting kit for walls, floors, roofs and benches for MODUL-CAB-Q 1180, -F 1180, -Q 1450, -F 1450, -R 1800/900, -R 1800/1180, -R 2065/1180

MODUL-KIT-CAB 2

Mounting kit for walls, floors, roofs and benches for MODUL-CAB-R 2370/1450



MODUL-KIT-CAB 1



MODUL-KIT-CAB 2




LUX ELEMENTS®-MODUL

■ PRODUCT SPECIFICATIONS – LUX ELEMENTS®-MODUL-CAB

MODUL-CAB, steam room construction, wall thickness 50 mm, wall height 2390 mm, roof shape FLAT, DOOR-TZ F-S (flat frame) with DOOR-GT-F-TK (glass door) and DOOR-TK (door knob), with integrated and sealed floor drain support frame 135 x 135 mm, bench form SOLO. Floor drain supports, see floor drain systems (page 68–75).


ARTICLE-NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	NOMINAL FORMATS/DIMENSIONS LENGTH x WIDTH x HEIGHT	UNIT
----------------	------------------------------------	--	------



MODUL-CAB-Q – quadratic cabin



MODUL-CAB-F – pentagonal cabin







MODUL-CAB-R – rectangular cabin


	LMODE202001	MODUL-CAB-Q 1180 Quadratic cabin as building kit, wall thickness 50 mm, wall height 2390 mm, roof shape FLAT, DOOR-TZ F-S (flat frame) with DOOR-GT-F-TK (glass door) and DOOR-TK (door knob), with integrated and sealed floor drain support frame 135 x 135 mm, bench shape SOLO	1180 x 1180 x 2390 mm	set
	LMODE203001	MODUL-CAB-F 1180 Pentagonal cabin as building kit, wall thickness 50 mm, wall height 2390 mm, roof shape FLAT, DOOR-TZ F-S (flat frame) with DOOR-GT-F-TK (glass door) and DOOR-TK (door knob), with integrated and sealed floor drain support frame 135 x 135 mm, bench shape SOLO quadrant	1180 x 1180 x 2390 mm	set
	LMODE202002	MODUL-CAB-Q 1450 Quadratic cabin as building kit, wall thickness 50 mm, wall height 2390 mm, roof shape FLAT, DOOR-TZ F-S (flat frame) with DOOR-GT-F-TK (glass door) and DOOR-TK (door knob), with integrated and sealed floor drain support frame 135 x 135 mm, bench shape SOLO	1450 x 1450 x 2390 mm	set
	LMODE203002	MODUL-CAB-F 1450 Pentagonal cabin as building kit, wall thickness 50 mm, wall height 2390 mm, roof shape FLAT, DOOR-TZ F-S (flat frame) with DOOR-GT-F-TK (glass door) and DOOR-TK (door knob), with integrated and sealed floor drain support frame 135 x 135 mm, bench shape SOLO quadrant	1450 x 1450 x 2390 mm	set
	LMODE201001	MODUL-CAB-R 1800/900 Rectangular cabin as building kit, wall thickness 50 mm, wall height 2390 mm, roof shape FLAT, DOOR-TZ F-S (flat frame) with DOOR-GT-F-TK (glass door) and DOOR-TK (door knob), with integrated and sealed floor drain support frame 135 x 135 mm, bench form SOLO	1800 x 900 x 2390 mm	set
	LMODE201002	MODUL-CAB-R 1800/1180 Rectangular cabin as building kit, wall thickness 50 mm, wall height 2390 mm, roof shape FLAT, DOOR-TZ F-S (flat frame) with DOOR-GT-F-TK (glass door) and DOOR-TK (door knob), with integrated and sealed floor drain support frame 135 x 135 mm, bench form SOLO	1800 x 1180 x 2390 mm	set

Contd. on page 137

■ PRODUCT SPECIFICATIONS – LUX ELEMENTS®-MODUL-CAB

	ARTICLE-NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	NOMINAL FORMATS/DIMENSIONS LENGTH x WIDTH x HEIGHT	UNIT
	LMODE201003	MODUL-CAB-R 2065/1180 Rectangular cabin as building kit, wall thickness 50 mm, wall height 2390 mm, roof shape FLAT, DOOR-TZ F-S (flat frame) with DOOR-GT-F-TK (glass door) and DOOR-TK (door knob), with integrated and sealed floor drain support frame 135 x 135 mm, bench form SOLO	2065 x 1180 x 2390 mm	set
	LMODE201004	MODUL-CAB-R 2370/1450 Rectangular cabin as building kit, wall thickness 50 mm, wall height 2390 mm, roof shape FLAT, DOOR-TZ F-S (flat frame) with DOOR-GT-F-TK (glass door) and DOOR-TK (door knob), with integrated and sealed floor drain support frame 135 x 135 mm, bench form SOLO	2370 x 1450 x 2390 mm	set
	LMODE204001	MODUL-KIT-CAB 1 Mounting kit for walls, floors, roofs and benches for MODUL-CAB-Q 1180, -F 1180, -Q 1450, -F 1450, -R 1800/900, -R 1800/1180, -R 2065/1180: 10 pieces FIX-SD 80, 30 kg COL-AK, 6 cartridges COL-MK, 60 m ARM-100 SK, 3,5 kg DRY-ASK, 4 pieces DRY-DBIE, 5 m DRY-DB, 10 hardwood wedges, 10 mounting brackets		Kit
	LMODE204002	MODUL-KIT-CAB 2 Mounting kit for walls, floors, roofs and benches for MODUL-CAB-R 2370/1450: 10 pieces FIX-SD 80, 30 kg COL-AK, 12 cartridges COL-MK, 90 m ARM-100 SK, 3,5 kg DRY-ASK, 4 pieces DRY-DBIE, 10 m DRY-DB, 10 hardwood wedges, 10 mounting brackets		Kit

System components FIX, COL, ARM, DRY · current price list page 78/79




Individual room constructions

Individually planned room constructions made of hard foam support material. We produce according to the customer's specifications or develop with you customer- or object-based solutions.

The room constructions are used both as hot air areas, e.g. steam baths, and as cold areas.







CONCEPT – the construction

A building kit from the CONCEPT product group may be comprised of the following components, for example:

- Roof
- Glass door
- Floor element
- Wall construction as kit
- Aluminium door frame
- Substrate element for floor element
- Seat
- Drain technology

Enhancements are possible with optional accessories such as a steam inlet or installation panel (see page 174). Assembly accessories are offered as complete kits for all available sizes.

**Roof, e.g.
CONCEPT-DA-BARREL**

**Wall construction
as kit**


**Frame, e.g.
CONCEPT-DOOR-TZ B**

Glass door

**Seat, e.g.
CONCEPT-BA-STEP**

Floor element

**Substrate element
for floor element**




Floor drain systems see page 68–75


Technical information concerning connections

The method of construction for the connection of the individual components ensures particularly high stability:


- Particularly stable panel connection thanks to tongue and groove principle
- Self-levelling panel connection thanks to V-groove
- Fast and simple assembly thanks to optimised fitting accuracy of the elements
- High production accuracy thanks to the use of state-of-the-art cutting technologies
- Stable fastening option for the door profile thanks to FIX-PRO-MAK over the entire panel width
- Flexible wall height: panel length up to 2500 mm, higher walls possible by using wall extension




Flexible wall height: higher walls possible by using wall extension




Wall extension and roof support with step seam




Panel connection consisting of tongue and V-groove



FIX-PRO-MAK 80 mm, circumferential on 3 sides of the door opening



Corners glued in the factory




Panel connection consisting of tongue and V-groove



Wall elements




Building kit for walls.

For the possibility to combine walls made of hard foam support material with a glass and metal construction, LUX ELEMENTS will supply a suitable design solution on enquiry.



Accessories, see page 174:


- **FIX-DE-...**
Supporting panel for a steam inlet
- **FIX-IPA-...**
Installation panel for the mounting of fittings



Floor elements


Floor elements with gradient and factory-fitted seal, alternatively for point or linear drainage.

For drain technology see LUX ELEMENTS®-TUB (page 68–75).



Substrate elements





Substrate elements, 55 mm thick.



Roofs

The following standard design variants are available:

- **CONCEPT-DA-BARREL**
the barrel roof design
- **CONCEPT-DA-CROSS**
the cross-vault roof shape
- **CONCEPT-DA-FLAT**
the simple flat roof shape
- **CONCEPT-DA-MONO**
the monopitch roof with panel








The seat variants

Nine standard design variants are offered for fitting with a bench. For the corner design choose either mitre (...EG) or curvature (...ER). Possible finishing elements: round segmented bench end (... AR), closed bench end (... BG) or a custom-made arm rest.


As an option, either a milling for the on-site installation of water heaters or an electrical heating set integrated at the factory with temperature sensor and temperature regulator can be ordered.





■ Bench form STEP




■ Bench form SIT





■ Bench form SLEEP






■ Bench form SOFT





■ Bench form SLIM





■ Bench form SOLO




■ Bench form STAR



■ Bench form SPACE





CONCEPT-BA-FLOAT

The CONCEPT-BA-FLOAT is a tileable seat variant in “floating” design, which makes the optical impression of more space, due to its filigree construction. The assembly of the bench takes place by way of a flexible, adaptable stainless steel substructure (straight or with corner elements).


A circumferential distance from the wall is maintained to allow the water to drain off. The bench seat is made to measure corresponding with the wall construction. Equipping with electric heating and/or indirect lighting is optionally possible (see page 147).

For further information please refer to the assembly instructions CONCEPT-BA-FLOAT.

The construction


e.g. CONCEPT-BA-FLOAT-GK

consisting of a bench element and ...



... a stainless steel substructure


The assembly



The assembly of the stainless steel substructure for CONCEPT-BA-FLOAT into the CONCEPT-WA... wall construction (see page 142) takes place via factory-made notches in the corner elements.

For this, a seat height of 45 cm is predefined (other heights possible upon request).

Hard foam filler elements are enclosed for the later covering of the cutouts.




CONCEPT-BA-FLOAT-G...

Bench form FLOAT, straight, between two walls, incl. stainless steel substructure.


- CONCEPT-BA-FLOAT-GK
from 1500 to 2100 mm
- CONCEPT-BA-FLOAT-GL
from 2100 to 3000 mm



CONCEPT-BA-FLOAT-GK




CONCEPT-BA-FLOAT-GL



CONCEPT-BA-FLOAT-E...

Complementary to FLOAT-G... :
Bench form FLOAT, straight, incl. stainless steel substructure for corner elements


- CONCEPT-BA-FLOAT-EK
from 1500 to 2100 mm
- CONCEPT-BA-FLOAT-EL
from 2100 to 3000 mm



CONCEPT-BA-FLOAT LL

An optional light strip enables indirect LED lighting underneath the bench seat CONCEPT-BA-FLOAT (surcharge). The scope of delivery includes:


- A control unit including radio remote control, by means of which different colours and colour change programs can be set.
- Prefabrication of the underside of CONCEPT-BA-FLOAT:
the seat support is fitted in the factory with a profile for mounting the light strip. A clamping mechanism enables easy insertion of the light strip and also later removal, e.g. for maintenance. The light strip consists of an aluminium U-profile housing with IP 65 protection and is thus protected against moisture.



CONCEPT-BA-EH


Electric heating set, integrated and embedded in filler at the factory, with temperature sensor and temperature regulator for bench form FLOAT, individually made to measure (surcharge).





Accessories

- Aluminium door frames, custom-made, as block profile (**DOOR-TZ B**) or flat profile (**DOOR-TZ F**, also available in standard size). Surface polished similar to stainless steel, anodised, with locking mechanism and hinges for glass doors.
- **CONCEPT-DOOR-GT** – Glass door ESG 8 mm, custom-made, or standard size, incl. drilling for door knob or handle bar.
- **CONCEPT-DOOR-TK** – Door knob similar to stainless steel, polished.
- **CONCEPT-DOOR-GS** – Stainless steel handle bar brushed.
- For suitable drainage see LUX ELEMENTS®-TUB, page 68–75.
- **FIX-DE-TI 28/FIX-DE-TE 28** or **FIX-DE-TI 45/FIX-DE-TE 45** – Supporting panel for a steam inlet, see page 174
- **FIX-DE-TI 110/FIX-DE-TE 110** – Supporting panel for a steam inlet, see page 174
- **FIX-IPA-I/FIX-IPA-E/FIX-IPA-V** – Installation panel for the mounting of fittings, see page 174



Accessories

- Various Mounting kits for wall and floor constructions, depending on the size.

CONCEPT-KIT-WA 1

for walls, roofs and benches up to a surface of approx. 4 m²

CONCEPT-KIT-WA 2

for walls, roofs and benches from approx. 4 m² up to a surface of approx. 9 m²

CONCEPT-KIT-WA 3

for walls, roofs and benches from approx. 9 m² up to a surface of approx. 14 m²

CONCEPT-KIT-BO 1

for floor structures up to a surface of approx. 4 m²

CONCEPT-KIT-BO 2

for floor structures from approx. 4 m² up to a surface of approx. 9 m²

CONCEPT-KIT-BO 3

for floor structures from approx. 9 m² up to a surface of approx. 14 m²



CONCEPT-KIT-WA 1



CONCEPT-KIT-WA 2



CONCEPT-KIT-WA 3



CONCEPT-KIT-BO 1



CONCEPT-KIT-BO 2







CONCEPT-KIT-BO 3



■ **PRODUCT SPECIFICATIONS – LUX ELEMENTS®-CONCEPT-BA-... (BENCHES)**

ARTICLE-NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	UNIT
----------------	---------------------------------------	------

				X = length to be ordered
CONCEPT-BA-...-G	CONCEPT-BA-...-G + CONCEPT-BA-...-EG	CONCEPT-BA-...-G + CONCEPT-BA-...-ER	CONCEPT-BA-...-G + CONCEPT-BA-...-AR	

	LCONBASTEP4001	CONCEPT-BA-STEP-G Bench form STEP, straight	running meter
	LCONBASTEP4002	CONCEPT-BA-STEP-EG , Bench form STEP, surcharge for corner element with mitre cut	surcharge
	LCONBASTEP4003	CONCEPT-BA-STEP-ER , Bench form STEP, surcharge for corner element, with round segments	surcharge
	LCONBASTEP4004	CONCEPT-BA-STEP-AR , Bench form STEP, surcharge for bench end, with round segments	surcharge
	LCONBASTEP4005	CONCEPT-BA-STEP-BG , Bench form STEP, surcharge for bench end closed	surcharge
	LCONBASIT4101	CONCEPT-BA-SIT-G Bench form SIT, straight	running meter
	LCONBASIT4102	CONCEPT-BA-SIT-EG , Bench form SIT, surcharge for corner element with mitre cut	surcharge
	LCONBASIT4103	CONCEPT-BA-SIT-ER , Bench form SIT, surcharge for corner element, with round segments	surcharge
	LCONBASIT4104	CONCEPT-BA-SIT-AR , Bench form SIT, surcharge for bench end, with round segments	surcharge
	LCONBASIT4105	CONCEPT-BA-SIT-BG , Bench form SIT, surcharge for bench end closed	surcharge
	LCONBASLEEP4201	CONCEPT-BA-SLEEP-G Bench form SLEEP, straight	running meter
	LCONBASLEEP4202	CONCEPT-BA-SLEEP-EG , Bench form SLEEP, surcharge for corner element with mitre cut	surcharge
	LCONBASLEEP4203	CONCEPT-BA-SLEEP-ER , Bench form SLEEP, surcharge for corner element, with round segments	surcharge
	LCONBASLEEP4204	CONCEPT-BA-SLEEP-AR , Bench form SLEEP, surcharge for bench end, with round segments	surcharge
	LCONBASLEEP4205	CONCEPT-BA-SLEEP-BG , Bench form SLEEP, surcharge for bench end closed	surcharge
	LCONBASOFT4301	CONCEPT-BA-SOFT-G Bench form SOFT, straight	running meter
	LCONBASOFT4302	CONCEPT-BA-SOFT-EG , Bench form SOFT, surcharge for corner element with mitre cut	surcharge
	LCONBASOFT4303	CONCEPT-BA-SOFT-ER , Bench form SOFT, surcharge for corner element, with round segments	surcharge
	LCONBASOFT4304	CONCEPT-BA-SOFT-AR , Bench form SOFT, surcharge for bench end, with round segments	surcharge
	LCONBASOFT4305	CONCEPT-BA-SOFT-BG , Bench form SOFT, surcharge for bench end closed	surcharge
	LCONBASLIM4401	CONCEPT-BA-SLIM-G Bench form SLIM, straight	running meter
	LCONBASLIM4402	CONCEPT-BA-SLIM-EG , Bench form SLIM, surcharge for corner element with mitre cut	surcharge
	LCONBASLIM4403	CONCEPT-BA-SLIM-ER , Bench form SLIM, surcharge for corner element, with round segments	surcharge
	LCONBASLIM4404	CONCEPT-BA-SLIM-AR , Bench form SLIM, surcharge for bench end, with round segments	surcharge
	LCONBASLIM4405	CONCEPT-BA-SLIM-BG , Bench form SLIM, surcharge for bench end closed	surcharge

Contd. on page 151


■ PRODUCT SPECIFICATIONS – LUX ELEMENTS®-CONCEPT-BA-... (BENCHES)

	ARTICLE-NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	UNIT
	LCONBASOLO4501	CONCEPT-BA-SOLO-G Bench form SOLO, straight	running meter
	LCONBASOLO4502	CONCEPT-BA-SOLO-EG , Bench form SOLO, surcharge for corner element with mitre cut	surcharge
	LCONBASOLO4503	CONCEPT-BA-SOLO-ER , Bench form SOLO, surcharge for corner element, with round segments	surcharge
	LCONBASOLO4504	CONCEPT-BA-SOLO-AR , Bench form SOLO, surcharge for bench end, with round segments	surcharge
	LCONBASOLO4508	CONCEPT-BA-SOLO-BG , Bench form SOLO, surcharge for bench end closed	surcharge
	LCONBASTAR4901	CONCEPT-BA-STAR-G Bench form STAR, straight	running meter
	LCONBASTAR4904	CONCEPT-BA-STAR-L , Bench form STAR, Rückenlehne	running meter
	LCONBASTAR4902	CONCEPT-BA-STAR-EG , Bench form STAR, surcharge for corner element with mitre cut	surcharge
	LCONBASTAR4903	CONCEPT-BA-STAR-AE , Bench form STAR, surcharge for bench end with mitre cut	surcharge
	LCONBASTAR4905	CONCEPT-BA-STAR-BG , Bench form STAR, surcharge for bench end closed	surcharge
	LCONBASPACE4211	CONCEPT-BA-SPACE-G Bench form SPACE, straight	running meter
	LCONBASPACE4212	CONCEPT-BA-SPACE-EG , Bench form SPACE, surcharge for corner element with mitre cut	surcharge
	LCONBASPACE4213	CONCEPT-BA-SPACE-ER , Bench form SPACE, surcharge for corner element, with round segments	surcharge
	LCONBASPACE4214	CONCEPT-BA-SPACE-AR , Bench form SPACE, surcharge for bench end, with round segments	surcharge
	LCONBASPACE4215	CONCEPT-BA-SPACE-BG , Bench form SPACE, surcharge for bench end closed	surcharge
	LCONBAFLOAT4801	CONCEPT-BA-FLOAT-GK Bench form FLOAT floating, straight, incl. stainless steel framework, from 1500 to 2100 mm	set
	LCONBAFLOAT4802	CONCEPT-BA-FLOAT-EK Bench form FLOAT floating, straight, incl. stainless steel framework from for corner element only in combination with CONCEPT-BA-FLOAT-GK, from 1500 to 2100 mm	set
	LCONBAFLOAT4804	CONCEPT-BA-FLOAT-GL Bench form FLOAT floating, straight, incl. stainless steel framework, from 2100 to 3000 mm	set
	LCONBAFLOAT4805	CONCEPT-BA-FLOAT-EL Bench form FLOAT floating, straight, incl. stainless steel framework from for corner element only in combination with CONCEPT-BA-FLOAT-GL, from 2100 to 3000 mm	set
	LCONBAL4701	CONCEPT-BA-L Arm rest as a finishing element for bench forms STEP, SIT, SLEEP, SOFT, SLIM, SOLO, STAR, SPACE, individually made to measure	piece
	LCONBAEH4601	CONCEPT-BA-EH Electrical heating set with temperature sensor and temperature regulator for bench forms STEP, SIT, SLEEP, SOFT, SLIM, SOLO, STAR, SPACE, FLOAT, individually made to measure als surcharge	set
	LCONBAFH4602	CONCEPT-BA-FH Millings for the on-site installation of water heaters for bench forms STEP, SIT, SLEEP, SOFT, SLIM, SOLO, SPACE, individually made to measure als surcharge	piece
	LCONBAFLOAT4803	CONCEPT-BA-FLOAT-LL Indirect lighting for bench form FLOAT, as a supplement	surcharge









LUX ELEMENTS®-CONCEPT

■ PRODUCT SPECIFICATIONS – LUX ELEMENTS®-CONCEPT-DOOR-... (DOORS)


	ARTICLE-NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	NOMINAL FORMATS/DIMENSIONS WIDTH x HEIGHT	UNIT
	LCONDOOR5001	CONCEPT-DOOR-TZ B Aluminium door frame three-section with lintel, block profile, surface simulated abraded stainless steel, anodised, with locking mechanism and hinges for glass doors	max. 1000 mm width, max. 2000 mm in height	piece
	LCONDOOR5002	CONCEPT-DOOR-TZ F Aluminium door frame three-section with lintel, flat profile, surface simulated abraded stainless steel, anodised, with locking mechanism and hinges for glass doors	max. 1000 mm width, max. 2000 mm in height	piece
	LCONDOOR5004	CONCEPT-DOOR-TZ F-S/R Aluminium door frame with lintel, flat section, surface polished similar to stainless steel, anodised, with locking mechanism and glass doors hinges, model DIN right, standard size	800 mm wide, 2000 mm high	piece
	LCONDOOR5005	CONCEPT-DOOR-TZ F-S/L Aluminium door frame with lintel, flat section, surface polished similar to stainless steel, anodised, with locking mechanism and glass doors hinges, model DIN left, standard size	800 mm wide, 2000 mm high	piece
	LCONDOOR5101	CONCEPT-DOOR-GT 800 Glass door ESG 8 mm made to measure, incl. drilling for door knob or handle bar	max. 800 mm width, max. 2000 mm in height	piece
	LCONDOOR5102	CONCEPT-DOOR-GT 1000 Glass door ESG 8 mm made to measure, incl. drilling for door knob or handle bar	max. 1000 mm width, max. 2000 mm in height	piece
	LCONDOOR5105	CONCEPT-DOOR-GT-F - TK Glass door ESG 8mm, standard size , suitable for CONCEPT-DOOR-TZ F-S, incl. drilling for door knob	774 mm wide, 1980 mm high	piece
	LCONDOOR5106	CONCEPT-DOOR-GT-F - GS Glass door ESG 8mm, standard size , suitable for CONCEPT-DOOR-TZ F-S, incl. drilling for handle bar	774 mm wide, 1980 mm high	piece
	LCONDOOR5010	CONCEPT-DOOR-TK Door knob similar to stainless steel, polished	Ø 45 mm	set
	LCONDOOR5011	CONCEPT-DOOR-GS Stainless steel handle bar brushed	300 mm long, Ø 20 mm	set

System components ARM, COL, DRY, FIX · current price list page 84

■ PRODUCT SPECIFICATIONS – LUX ELEMENTS®-CONCEPT-KIT



	ARTICLE-NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	UNIT
	LCONKIT6001	CONCEPT-KIT-WA 1 Mounting kit for walls, roofs and benches up to a surface of approx. 4 m ² : 20 pieces FIX-SD 80, 40 kg COL-AK, 12 cartridges COL-MK, 90 m ARM-100 SK, 15 timber wedges, 15 mounting brackets	Kit
	LCONKIT6002	CONCEPT-KIT-WA 2 Mounting kit for walls, roofs and benches from approx. 4 m ² up to a surface of approx. 9 m ² : 40 pieces FIX-SD 80, 75 kg COL-AK, 18 cartridges COL-MK, 120 m ARM-100 SK, 15 timber wedges, 15 mounting brackets	Kit
	LCONKIT6201	CONCEPT-KIT-WA 3 Mounting kit for walls, roofs and benches from approx. 9 m ² up to a surface of approx. 14 m ² : 50 pieces FIX-SD 80, 95 kg COL-AK, 24 cartridges COL-MK, 180 m ARM-100 SK, 15 timber wedges, 15 mounting brackets	Kit
	LCONKIT6101	CONCEPT-KIT-BO 1 Mounting kit for floor structures up to a surface of approx. 4 m ² : 1 cartridge COL-MK, 50 kg COL-AK, 3,5 kg DRY-ASK, 10 m DRY-DB, 4 pieces DRY-DBIE	Kit
	LCONKIT6102	CONCEPT-KIT-BO 2 Mounting kit for floor structures from approx. 4 m ² up to a surface of approx. 9 m ² : 1 cartridge COL-MK, 100 kg COL-AK, 7 kg DRY-ASK, 20 m DRY-DB, 4 pieces DRY-DBIE	Kit
	LCONKIT6202	CONCEPT-KIT-BO 3 Mounting kit for floor structures from approx. 9 m ² up to a surface of approx. 14 m ² : 3 cartridges COL-MK, 100 kg COL-AK, 20 kg DRY-ASK, 40 m DRY-DB, 4 pieces DRY-DBIE	Kit

CONCEPT-KIT... : RANGE OF APPLICATION	Mounting kit for walls, roofs and benches	Mounting kit for floor structures
up to a surface of approx. 4 m ²	CONCEPT-KIT-WA 1	CONCEPT-KIT-BO 1
from approx. 4 m ² up to a surface of approx. 9 m ²	CONCEPT-KIT-WA 2	CONCEPT-KIT-BO 2
from approx. 9 m ² up to a surface of approx. 14 m ²	CONCEPT-KIT-WA 3	CONCEPT-KIT-BO 3






From planning to finished item:

- Idea, sketch or detailed draft from customer
- Assistance from LUX ELEMENT regarding detailed questions
- Preparation of a technical drawing for approval with 3D view at LUX ELEMENTS
- If necessary LUX ELEMENTS will carry out static calculations
- Manufacture of the individual components exactly in accordance with planning specifications
- Test assembly at LUX ELEMENTS and numbering of the components
- Delivery to the building site in segments
- Assembly by installer



You can give free rein to your ideas at the planning stage. The modern, flexible production methods at LUX ELEMENTS make it possible to produce large items and a wide range of shapes.







LUX ELEMENTS®-CONCEPT

Complete solutions from one source or individual custom products can be designed with hard foam support elements from LUX ELEMENTS.

For the possibility to combine walls made of hard foam support material with a glass and metal construction, LUX ELEMENTS will supply a suitable design solution on enquiry.







The decorative elements

DECO are decorative elements of hard foam support material with which products of LUX ELEMENTS as well as rooms, walls, corners etc. can be equipped, clad or supplemented.




LUX ELEMENTS®-DECO-PLUS

LUX ELEMENTS manufactures individual customised and special products for the DECO product group. These include dimensions, thicknesses, shapes etc. that deviate from the standard program. For more information see page 8.



















The concave trims

Concave trims are fitted in corners for rounding off inwards e.g. in steam rooms, showers (see RELAX-JUNIOR) and room corners. The DECO-RD-HK concave trim is used as a round shower fitting part to the wall. In this way an acute-angled gap is covered.



The curvature elements







The DECO-AE semi-circular finishing element can be ordered to round off edges e.g. with RELAX-RD, RELAX-SD and RELAX-RSE (s. pages 110–119). The DECO-VE round cladding element in two sizes is used to round off corners outwards.






The pillars (columns)

Columns are available as round models (PM R) for freestanding columns, half-round models (PM H) for wall mounting, and quadrant-shaped models (PM-V) for room corners. The diameter is 240 mm, the length is 2500 mm.



■ PRODUCT SPECIFICATIONS – LUX ELEMENTS®-DECO

	ARTICLE-NUMBER	ARTICLE-NAME / ARTICLE-DESCRIPTION	NOMINAL FORMATS/DIMENSIONS	UNIT
	LDECE1001	DECO-HK 100 Concave trims	Radius 100 mm, length 2500 mm	piece
	LDECE1002	DECO-HK 200 Concave trims	Radius 200 mm, length 2500 mm	piece
	LDECE1003	DECO-RD-HK Round showers wall connection concave trim for RELAX-RD	Radius 100 mm, height 2500 mm	piece
	LDECE2001	DECO-PM R Column, modern design, round	Ø 240 mm, length 2500 mm	piece
	LDECE2002	DECO-PM H Column, modern design, semi-circular	Ø 240 mm, length 2500 mm	piece
	LDECE2003	DECO-PM V Column, modern design, quadrant	Ø 240 mm, length 2500 mm	piece
	LDECE3001	DECO-VE 200 Round surrounding element for corners	Ø 200 mm, length 2500 mm	piece
	LDECE3002	DECO-VE 120 Round surrounding element for corners	Ø 120 mm, length 2500 mm	piece
	LDECE3003	DECO-AE Finishing element for edges	Ø 120 mm, length 2500 mm	piece

System components ARM, COL, DRY · current price list page 86



LUX ELEMENTS®-DECO



LUX ELEMENTS®-DECO-PLUS

LUX ELEMENTS manufactures individual customised and special products for the DECO product group. These include dimensions, thicknesses, shapes etc. that deviate from the standard program. For more information see page 8.












The foam parts

The basic material for the products of LUX ELEMENTS is LUX ELEMENTS®-FOAM, a very high-quality, blue coloured, expanded polystyrene hard foam with high density that is produced using an **environmentally friendly technique** without foaming agents which are harmful to the climate.









LUX ELEMENTS®-FOAM

The good workability of this material and the production methods at LUX ELEMENTS enable individual and complex shapes to be manufactured.

The lightweight, waterproof and mold-resistant polystyrene hard foam can be used in various areas. Therefore a mortar coating is not always necessary.

Uncoated FOAM is available upon request as:

- Block
- Panel blank
- Shaped part



SNITT C-E
MÄTTSÄTTNING
SKALA 1:10

